



NOTES:

1. TEMP BF/RP MUST BE CERTIFIED BY A CITY APPROVED TESTER
2. ALL BACTERIA SAMPLES MUST BE TAKEN BY A LAB CERTIFIED BY THE CITY OF MADERA
3. BACTERIA TEST SITES SHALL BE NO MORE THAN 350 FEET APART
4. BF/RP, BLOW-OFF AND TEST PLATES ARE TO BE REMOVED ONLY AFTER FIRST BACTERIA TEST HAS PASSED. IF A TEST FAILS AT ONE TEST SITE, ALL SITES MUST BE RE-TESTED
5. BLOW OFF SYSTEM AND TURN OFF ALL LINE VALVES TO NEW WATER MAIN FOR 24 HOURS AND CONDUCT A SECOND SET OF BACTERIA TESTS. IF A TEST FAILS AT ONE TEST SITE, ALL SITES MUST BE RE-TESTED
6. TURN ON ALL LINE VALVES ONLY AFTER SECOND SET OF BACTERIA TESTS HAVE PASSED
7. FOR MORE INFORMATION AND REQUIREMENTS SEE WRITTEN SPECIFICATIONS 22-9, "TESTING AND STERILIZATION"