

ALLOW A MINIMUM OF 48 HOURS FOR CONCRETE TO SET BEFORE BACKFILLING

BACKFILL WITH NATIVE SOIL OR EQUIV., FREE OF LARGE ROCKS AND DEBRIS 3" DIA. OR LARGER, MECHANICALLY COMPACTED IN 12" MAX. LIFTS.

